



ADDENDUM NO. 2

October 15, 2021

REPAIRS TO THE
WESTBROOK HEAD START CENTER
MCCOMB, MISSISSIPPI
MISSISSIPPI ACTION FOR PROGRESS, INC.

The following changes and/or clarifications have been made in the above named project and wherever the plans and specifications are inconsistent, this Addendum shall govern:

“REFER TO PLANS”

- 1) Sheet E1 of 1 - Electrical
 - a) The symbol ‘CA’ denotes camera locations either new or existing to be relocated.
 - b) The symbol ‘S’ denotes smoke detector locations with new or existing to be relocated.
 - c) Contractor shall lower the smoke detectors in Classrooms 5, 6, and 7 under Alternate No. 1.
 - d) Contractor shall replace the existing Desk Top Control Console.
 - e) Contractor shall lower the existing intercom speakers in each room as required where ceilings are lowered.
 - f) Contractor shall provide new speakers and call switches in two of the four rooms to be used by Early Head Start in the southeast corner of the building. Relocate the four existing to the remaining rooms in the area.

“REFER TO SPEC’S”

- 1) SECTION 08520 – Alum. Windows - Delete
- 2) SECTION 08850 – Glass and Glazing – Delete
- 3) SECTION 10101- Tackboards – Delete
- 4) SECTION 10250 – Firefighting Devices – Delete
- 5) SECTION 09500 – Acoustical Ceiling Systems
 - a) Change the grid and tile to a 24”x24” system. Using Armstrong Fine Fissured Square Lay-In #1729.
- 6) SECTION 23735 – Split System HVAC Units – Delete.

* * * END OF ADDENDUM * * *

server/brenda/word/map/westbrook/addendum 2